

SZ-150-36MF

Warranty

- ◆ 2 years Manufacturer Warranty
- ◆ Warranty on Electrical Performance: 5 years 80% of power output

Manufacturing

- ◆ Original cell sorting system ensures the best electric cell match
- ◆ EL-Testing before packing.
- ◆ Comprehensive module power testing.

Performance

- ◆ Upgraded efficiency and unprecedented flexibility.
- ◆ Weakened hot-spot effect, extremely low risk of micro cracks and increased stability by shingle-tech.
- ◆ Special connection method lowers the internal resistance and ensures better performance than traditional connection with busbar.
- ◆ IP67 rated junction box, reliable cables and standard MC4 connectors improve the stability



Mechanical Data

Standard Test Conditions AM=1.5, E=1000W/m², TC=25°C

Nominal Power	150W
Cell Type	Monocrystalline
Module Efficiency	18.81%
Maximum Power Current (Impp)	6.99A
Maximum Power Voltage (Vmpp)	21.45V
Open-circuit Voltage (Voc)	25.35V
Short-circuit Current (Isc)	7.51A
Maximum System Voltage	100V
Output Tolerance	±3%
Cable	700mm / 2.5mm ²
Connector Type	MC4 / MC4 Compatible
Module Structure	TPT / EVA / Backsheet
Junction box rating	≥IP67
Number of Diodes	Two
Working Temperature	-20°C~+65°C

Packaging

Module Dimensions	1240*670*2mm
Module Weight	2.90kg
Package	Single Package
Pieces per Pallet	32
Gross Weight per Pallet	125kg
Pallet Dimensions	1200*1100*800mm

SOLMAX NEW ENERGY B.V.

Address: Zonnebaan 23, 3542 EB Utrecht, the Netherlands

Tel: +31-307855708

Email: info@solarfam.nl

